



TOWN OF
PEACE RIVER
ALBERTA

Peace River Museum 2023 Re-Roof Project

Bid Closing: June 21, 2023, at 2:00 p.m.

Completion Date: July 30, 2023

1. Delete & Seal SBS NW scupper and down-pipe on Area-D.
2. Allow for New Gooseneck Vents.
3. Trim Wood Siding as Needed to Accommodate New Insulation Thickness
4. Remove Area-C Roof System and Decking.
5. Area-C: Install New 5/8" Plywood Deck.
 1/2" Densdeck Prime
 Carlisle VapAir Seal 725 TR
 Sloped MEPS Package 2" Minimum Thickness
 TPO Manufacturers Polyiso One Layer 2 1/2" (Flexible Fast Adhered)
 1/2" Densdeck Prime
 Fully Adhered Carlisle Sure-Weld 60-mil TPO Membrane
 Four Sided Soldered Scupper with ABS Down-Pipe. (Allow 30°)
6. Roofing Contractor must have its own washroom on site.
7. Owner will Remove and Reinstall Gas Lines.
8. Area- B Overflow 4" Thaler RD-240A Aluminum Drain through West Wall.
9. Area- C Overflow 4" Thaler RD-240A Aluminum Drain through South Wall.

Consultant: All Peace Roof Inspections Ltd.
Box 1791, Fairview
Alberta, T0H 1L0
Phone: 780-618-7790